April 4, 2025

ADDENDUM NO. 2

Pavement Management Program 2025 (Asphalt)
CIP Project No. 336-31704

NOTICE TO BIDDERS:

The following clarifications, amendments, additions and/or deletions as set forth herein shall apply to the above documents and shall be made a part thereof and shall be subject to all the requirements thereof as though originally specified and/or shown. Submitters shall assure themselves that all addendum changes have been incorporated into their proposal.

A. ADDITIONS/DELETIONS

1. **Replace** Section 5 of the Contract (page 22) with the following:

   5. **Time for Completion.** Contractor will fully complete the Work for the Project, meeting all requirements for Final Completion, within 60 calendar days from the start date set forth in the Notice to Proceed ("Contract Time"). By signing below, Contractor expressly waives any claim for delayed early completion.

2. **Replace** the following Section 01310 1.1D, Construction Schedule, in the Technical Specifications.

   D. All work shall be completed by July 31, 2025

3. **Replace** Bid Schedule (page 13-14) of the Bid Proposal with the revised Bid Schedule, herein attached.

B. CLARIFICATIONS

1. Clarification on the Reclaimed Asphalt Pavement (RAP) Allowance. Specifications reference current Caltrans spec which allows for 25% RAP. Section 03400 Asphalt Concrete 1.1 A references to maximum 15% RAP. Will the City of Brentwood allow for 25% RAP in the asphalt concrete designed to latest Caltrans edition for this project?

   The City will not allow 25% RAP on this project. The maximum RAP allowed will be 15%.

2. Spec Section 03400 – 3.2D of the above-mentioned project states, "The City reserves the first right to the AC grindings." but does not specify a location of where these grindings are to be stockpiled. Please confirm if the City will be taking possession of the AC grindings, and if so, provide a stockpile location so trucking can be priced appropriately.

   The City will not be taking the AC grindings for this project.

3. Will this project be awarded based on Base + Alt or Base bid alone?

   As stated in the Instructions to Bidders Section 19, "The lowest bid will be the lowest bid price on the base contract without consideration of the prices on the additive or deductive items."

4. Are you able to clarify the following… there is no line item or detail from what I can see for pavement fabric but the spec 3.6 (page 148) is saying GP50 is to be installed. Does that

apply to this project or is it boilerplate verbiage IF fabric is shown on the drawings (which it doesn't seem to be)?

Pavement fabric will be required along all areas receiving a grind and overlay. Pavement Fabric shall be included in the bid price for Asphalt Concrete (Bid Item #9).

All bidders shall acknowledge receipt and acceptance of Addendum No. 2 in the space provided on the Bid Proposal page 10 of the Contract Documents.

-END OF ADDENDUM NO. -2-

Brant Wilson, P.E.
Senior Associate Engineer

Revised Bid Schedule

This Bid Schedule must be completed in ink and included with the sealed Bid Proposal. Pricing must be provided for each Bid Item as indicated. Items marked "(SW)" are Specialty Work that must be performed by a qualified Subcontractor. The lump sum or unit cost for each item must be inclusive of all costs, whether direct or indirect, including profit and overhead. The sum of all amounts entered in the "Extended Total Amount" column must be identical to the Base Bid price entered in Section 1 of the Bid Proposal form.

AL = Allowance CF = Cubic Feet CY = Cubic Yard EA = Each LB = Pounds
LF = Linear Foot LS = Lump Sum SF = Square Feet TON = Ton (2000 lbs)

BID ITEM NO.	ITEM DESCRIPTION	EST. QTY.	UNIT	UNIT COST	EXTENDED TOTAL AMOUNT
1	Mobilization	1	LS	$	$
2	Traffic Control	1	LS	$	$
3	Storm Water Erosion/Pollution Control Plan	1	LS	$	$
4	Class 2 Aggregate Base	50	TON	$	$
5	Type II Slurry Seal	126,580	SY	$	$
6	2" Grind	57,590	SF	$	$
7	2.5" Grind	257,900	SF	$	$
8	4" Dig Out	8,890	SF	$	$
9	Asphalt Concrete	5,260	TON	$	$
10	Crack Seal	1	LS	$	$
11	Detail 9 (thermoplastic)	1,120	LF	$	$
12	Detail 22 (thermoplastic)	3,700	LF	$	$
13	Detail 24 (thermoplastic)	3,950	LF	$	$
14	Detail 27B (thermoplastic)	1,600	LF	$	$
15	Detail 29 (thermoplastic)	1,110	LF	$	$
16	Detail 32 (thermoplastic)	725	LF	$	$
17	Detail 38 (thermoplastic)	1,140	LF	$	$
18	Detail 39 (thermoplastic)	1,350	LF	$	$
19	Detail 39A (thermoplastic)	150	LF	$	$
20	12" White (thermoplastic)	2,000	LF	$	$
21	12" Yellow (thermoplastic)	1,500	LF	$	$
22	Pavement Markings (thermoplastic)	3,100	SF	$	$
23	Detail BL (thermoplastic)	6,250	LF	$	$
24	Adjust Existing Water Valve to Grade	29	EA	$	$
25	Adjust Existing Monument to Grade	2	EA	$	$

BID ITEM NO.	ITEM DESCRIPTION	EST. QTY.	UNIT	UNIT COST	EXTENDED TOTAL AMOUNT
26	Adjust Existing Sanitary Sewer Manhole to Grade	28	EA	$	$
27	Adjust Existing Storm Drain Manhole to Grade	2	EA	$	$
28	Replace Loop Detectors	1	EA	$	$
29	2.5" Grind – Elkins Way	8,370	SF	$	$
30	Asphalt Concrete – Elkins Way	140	TON	$	$

* Final Pay Quantity

TOTAL BASE BID: Items 1 through 30 inclusive: $_____

Note: The amount entered as the "Total Base Bid" should be identical to the Base Bid amount entered in Section 1 of the Bid Proposal form.

BID ALTERNATE #1 – SUNSET PARK PARKING LOT IMPROVEMENTS

BID ITEM NO.	ITEM DESCRIPTION	EST. QTY.	UNIT	UNIT COST	EXTENDED TOTAL AMOUNT
31	2" Grind – Sunset Parking Lot	11,100	SF	$	$
32	Asphalt Concrete – Sunset Park Parking Lot	185	TON	$	$
33	6" White (thermoplastic)	360	LF	$	$

TOTAL BID ALTERNATE #1 – SUNSET PARK PARKING LOT IMPROVEMENTS: Items 31 through 33 inclusive: $_____

*Note: The amount entered as the "*TOTAL BID ALTERNATE #1 – SUNSET PARK PARKING LOT IMPROVEMENTS*" should be identical to the Bid Alternate #1 amount entered in Section 2 of the Bid Proposal form.*

BIDDER NAME: _____

END OF BID SCHEDULE