



December 30, 2025

ADDENDUM NO. 2/CLARIFICATION NO. 2

Municipal Services Center Pavement Rehab

NOTICE TO BIDDERS:

The following clarifications, amendments, additions and/or deletions as set forth herein shall apply to the above documents and shall be made a part thereof and shall be subject to all the requirements thereof as though originally specified and/or shown. Submitters shall assure themselves that all addendum changes have been incorporated into their proposal.

A. CLARIFICATIONS

1. For 2" grind and overlay for area 1 on the plans, the legend states 222,000 SF while it measures at 46,000 SF per the scale. Please Clarify.

The correct SF for the 2" grind and overlay in Area 1 is 22,200 SF. This was a typographical error on the plans and does not affect the bid item quantity.

2. For the parking area, it states only 2.5" grind and overlay but no demolition. Should we include demolition and subgrade preparation?

Yes. Include all excavation, demolition, removal and disposal of excess materials, and subgrade preparation under bid item #8.

3. The GlassGrid called out in the specbook requires a leveling course to be applied before it can be installed and the current section is only 2". How would you like us to proceed?

The dig outs will be used to correct uneven areas and provide a smooth surface for the pavement fabric. The pavement fabric is to be placed at 2" depth. No separate leveling course is required.

4. Does the City have a proposed phase plan?

No phasing plan is proposed.

5. Special Conditions 1.2 state Authorized Working Days Times of 4:00 PM to 12:00 AM. Has this changed to 2:00 PM?

Pavement operations may begin at 2:00 PM. All other work shall remain subject to the authorized working hours of 4:00 PM to 12:00 AM.

ENGINEERING DEPARTMENT

150 City Park Way, Brentwood, CA 94513
Phone 925.516.5420 FAX 925.516.5421
www.brentwoodca.gov

6. Is parking lot A the 2.5" HMA Area? (Sheet 2)


Yes.

7. Are the paving fabric and geogrid required under all pavement areas? Can you provide details?

No Geogrid is required. See Response #3 for the paving fabric requirements.

All bidders shall acknowledge receipt and acceptance of Addendum No. 2 in the space provided on the Bid Proposal page 8 of the Contract Documents.

-END OF ADDENDUM NO. -2-



Brant Wilson
Project Manager